# Mendocino Coast District Hospital

SPC/NPC Overview Presentation I 05.05.2023



# Agenda Adventist Mendocino Coast

1.Review Definition of SPC & NPC2.Review SPC Upgrades On Campus3.Review NPC Upgrades On Campus4.Review New Hospital Construction5.Review Pricing



#### SPC & NPC Updates

Adventist Mendocino Coast

#### **GENERAL**

BUILDINGS ON CAMPUS RANKED BETWEEN 2-5 FOR SPC & NPC BY HCAI (CALIFORNIA DEPARTMENT OF HEALTHCARE ACCESS AND INFORMATION)

BUILDINGS REQUIREMENTS TO BE MET BY JAN. 1, 2030:

SPC < 2 UPGRADED TO SPC 4D

NPC < 2 UPGRADED TO NPC 4D

**SPC** 

**NPC** 



#### SPC & NPC Updates

Adventist Mendocino Coast

#### **GENERAL**

BUILDINGS ON CAMPUS RANKED BETWEEN 2-4 FOR SPC & NPC BY HCAI (CALIFORNIA DEPARTMENT OF HEALTHCARE ACCESS AND INFORMATION)

BUILDINGS REQUIREMENTS TO BE MET BY JAN. 1, 2030:

SPC < 2 UPGRADED TO SPC 4D

NPC < 2 UPGRADED TO NPC 4D

#### **SPC**

STRUCTURAL PERFORMANCE CATEGORY

REQUIREMENTS INCLUDE:
UPGRADING STRUCTURAL
ELEMENTS INCLUDING
FOUNDATION, COLUMNS, ETC

#### **NPC**



#### SPC & NPC Updates

Adventist Mendocino Coast

#### **GENERAL**

BUILDINGS ON CAMPUS RANKED BETWEEN 2-4 FOR SPC & NPC BY HCAI (CALIFORNIA DEPARTMENT OF HEALTHCARE ACCESS AND INFORMATION)

BUILDINGS REQUIREMENTS TO BE MET BY JAN. 1, 2030:

SPC < 2 UPGRADED TO SPC 4D

NPC < 2 UPGRADED TO NPC 4D

#### **SPC**

STRUCTURAL PERFORMANCE CATEGORY

REQUIREMENTS INCLUDE: UPGRADING STRUCTURAL ELEMENTS INCLUDING FOUNDATION, COLUMNS, ETC

#### **NPC**

NON-STRUCTURAL PERFORMANCE CATEGORY

REQUIREMENTS INCLUDE:
INFRASTRUCTURE BRACING AND
EQUIPMENT ANCHORAGE ALONG
WITH UPGRADING WATER & FUEL
STORAGE TANKS ON CAMPUS



### Overview | SPC/NPC Site Plan

Adventist Mendocino Coast

#### **OVERALL (HCAI) CAMPUS:**







#### **2030 SPC NON-COMPLIANT:**








#### **2030 NPC NON-COMPLIANT:**












### Seismic Upgrade Process

Adventist Mendocino Coast



Adventist Mendocino Coast



NEW CONCRETE EXPANSION ANCHORS


ROOF COLLECTOR STRENGTHENING

NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST


NEW PLYWOOD SHEATHING @ CEILING

NEW CABLE SPACING IN ATTIC ABOVE

**NEW SEISMIC GAP BETWEEN BUILDING** 








### SPC | Impacts

Adventist Mendocino Coast



# NEW HOLDOWN NEW CONCRETE EXPANSION ANCHORS

- CONSTRUCTION WILL HAPPEN WITHIN MOST SUPPORT ROOMS LIMITING IMPACT TO OPERATIONS
- AT TUB ROOMS OR SHOWER ROOM THE CONSTRUCTION WILL HAPPEN IN CORRIDOR TO NOT REQUIRE ACCESSIBILITY UPGRADES TO ROOM
- AT CORRIDOR CONSTRUCTION TEMPORARY INFECTION CONTROL BARRIERS WILL BE NEEDED AND MAY IMPACT OPERATIONS THROUGH CORRIDOR



Adventist Mendocino Coast



**NEW CONCRETE EXPANSION ANCHORS** 


**ROOF COLLECTOR STRENGTHENING** 

**NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST** 

**NEW PLYWOOD SHEATHING @ CEILING** 

**NEW CABLE SPACING IN ATTIC ABOVE** 

**NEW SEISMIC GAP BETWEEN BUILDING** 






### SPC | Impacts

Adventist Mendocino Coast

# ROOF COLLECTOR STREGTHENING NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST

- WORK WITHIN PATIENT ROOM
  WILL REQUIRE UPGRADE TO
  10% OF PATIENT ROOMS TO BE
  ACCESSIBLE, APPROXIMATELY
  (3) ROOMS
- REQUIRES APPROXIMATELY
   1,000 SF OF CONSTRUCTION



Adventist Mendocino Coast



NEW CONCRETE EXPANSION ANCHORS


**ROOF COLLECTOR STRENGTHENING** 

NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST


NEW PLYWOOD SHEATHING @ CEILING

NEW CABLE SPACING IN ATTIC ABOVE

**NEW SEISMIC GAP BETWEEN BUILDING** 








### SPC | Impact

Adventist Mendocino Coast

### NEW PLYWOOD SHEATHING @ CEILING

- CONSTRUCTION WILL HAPPEN ABOVE CEILING
- MOST WORK IS IN ADMIN AREA AND FRONT LOBBY
- LARGEST IMPACT TO OCCUR IN PHARMACY



Adventist Mendocino Coast



NEW CONCRETE EXPANSION ANCHORS


**ROOF COLLECTOR STRENGTHENING** 

NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST


NEW PLYWOOD SHEATHING @ CEILING

NEW CABLE SPACING IN ATTIC ABOVE

**NEW SEISMIC GAP BETWEEN BUILDING** 








### SPC | Impacts

Adventist Mendocino Coast

### NEW CABLE SPACING IN ATTIC ABOVE

- CONSTRUCTION WILL HAPPEN IN ATTIC
- MOST WORK IS ABOVE SUPPORT AREAS NOT IMPACTING OPERATIONS
- LARGEST IMPACT TO OCCUR IN SURGERY – CONSTRUCTION TO BE COORDINATED AROUND SURGERY TIME TO NOT DISRUPT OPERATIONS



Adventist Mendocino Coast



NEW CONCRETE EXPANSION ANCHORS


ROOF COLLECTOR STRENGTHENING

NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST

NEW PLYWOOD SHEATHING @ CEILING

NEW CABLE SPACING IN ATTIC ABOVE


**NEW SEISMIC GAP BETWEEN BUILDING** 





Adventist Mendocino Coast






### SPC | Impacts

Adventist Mendocino Coast

#### **NEW SEISMIC GAP BETWEEN BUILDING**

- CONSTRUCTION REQUIRES ADDING SEISMIC GAP AND **SEISMIC CONNECTIONS OF UTILITIES BETWEEN CANOPY** FROM CUP AND MAIN **HOSPITAL BUILDING**
- WILL IMPACT ALL UTILITIES **GOING INTO THE FACILITY** FROM CUP
- POTENTIAL TO LOSE UTILITIES **DURING CERTAIN TIMES DURING CONSTRUCTION**



Adventist Mendocino Coast



NEW CONCRETE EXPANSION ANCHORS


ROOF COLLECTOR STRENGTHENING

NEW STRAP AND 4' SCAB ALONG SIDE OF ROOF JOIST

NEW PLYWOOD SHEATHING @ CEILING

NEW CABLE SPACING IN ATTIC ABOVE

**NEW SEISMIC GAP BETWEEN BUILDING** 





#### NPC | Overview

Adventist Mendocino Coast

#### **NPC**

NON-STRUCTURAL PERFORMANCE CATEGORY

REQUIRES NON-STRUCTURAL COMPONENTS IN CRITICAL CARE AREAS, CLINICAL LABORATORY SERVICES SPACES, PHARMACEUTICAL SERVICE SPACES, RADIOLOGICAL SERVICE SPACES, AND CENTRAL AND STERILE SUPPLY AREAS ARE BRACED TO SATISFY THE REQUIREMENTS OF THE 1995 CBC, PART 2, TITLE 24 TABLE 16A-O.

GENERAL



Adventist Mendocino Coast

- Bracing Compliance is organized into the following categories
  - Equipment:
    - Storage racks over 5 feet tall
    - Permanent floor supported cabinets and book stacks over 5 feet tall
    - Access floor systems
    - Wall hung cabinets and storage shelving
    - Tanks and vessels
    - Electrical, mechanical and plumbing equipment necessary for continuing operation of the facility
    - Hospital (Medical) equipment when permanently attached to the building utility services
  - Suspended Ceiling and light fixtures
  - Piping distribution systems necessary for the continuing operation of the facility
  - Sprinkler Systems



### NPC | Timeline Requirements

Adventist Mendocino Coast

#### January 2 **2024**

Deadline to submit the non-structural evaluations (surveys) for NPC-4D Level 1 Minimum

#### January 1 **2028**

Deadline for Building Permit to perform upgrade work



Deadline to submit contract documents needed for NPC-4D Level 1 upgrade projects

#### January 2 **2028**

Starting on this date, all remodel projects located in buildings with rating less than NPC -4D or where structural rating is SPC-4D, will need to pick up all NPC-4 deficiencies within the project boundaries (slab to slab)



Adventist Mendocino Coast

• Intent of Scoping Study is to provide high level scoping of NPC-4D bracing required by 2030 with a limited timeframe – work did not include a nonstructural component survey in the field or a comprehensive review of all projects.

STEP 1:
STEP 2:
STEP 3:
STEP 4:
STEP 5:



Adventist Mendocino Coast

#### **STEP 1:**

Categorize each building based on year of design code and type of permit, which is primary indicator of extent of NPC work required within the building. Main Categories are:

PRE 1973

Buildings not permitted by OSA or OSHPD. Components are generally not in compliance with 2030 requirements and require bracing.

1984-1994 Building Permitted by OSHPD, but fire sprinkler bracing requirements are not considered compliant. Extent of work required by 2030 consists of end of line sway bracing for sprinkler branch lines

1973-1983 Buildings permitting by OSA, which covers NPC compliance. Extent of work varies by 2030 and depends on extent of bracing enforced during original construction.

POST 1994

Buildings permitting by OSHPD. Compliant and no work required by 2030

STEP 2:

STEP 3:

STEP 4:



Adventist Mendocino Coast

#### STEP 1:

#### **STEP 2:**

- Identify type and size of critical care area included within each building.
- Intent of step is to identify the extent of critical care departments at the facility within each category of building. Many critical care departments tend to be located in newer buildings resulting in less overall bracing required at the facility.

STEP 3:

**STEP 4:** 



Adventist Mendocino Coast

#### STEP 1:

#### STEP 2:

#### **STEP 3:**

- Outline Boundaries of critical care departments within each building on floor plans provided
- The boundaries consider the extent of departments that fall within the critical care definitions of the CBC

#### STEP 4:



Adventist Mendocino Coast

СТ		1
	P	

STEP 2:

STEP 3:

#### **STEP 4:**

- Prepare matrix that includes extent of departments within each building
- The year of construction provides baseline level of bracing compliance
- Matrix Contents:
  - Departments
  - Identified Project Notes Estimated nonstructural compliance
  - For each Department an estimated % Compliance
  - Summary information by campus and building



Adventist Mendocino Coast

STEP 1:

STEP 2:


STEP 3:

**STEP 4:** 

- Review select remodel document and visit site to identify extent of bracing under past projects that reduce the extent of nonstructural bracing work required by 2030
- Information is covered in notes and defines the percent of bracing compliance



## NPC | Scoping Study



LEGEND:

PRE-1973

GROUI

### NPC | Scoping Study

Adventist Mendocino Coast

LEGEND:

PRE-1973 OSA (1973-1983) F.S. Only (1983-1994) OSHPD Compliant (1994-Present)

\*No hatching indicates non NPC-4D area

#### Campus Totals

 Pre-1973 Areas =
 8100 sf

 1973-1983 OSA Permit Areas =
 sf

 1984-1994 F.S. Only Areas =
 4200 sf

 NPC-4D Level 1 Compliant =
 1300 sf

 No Work Required for NPC-4D Level 1 compliance =
 42900 sf

 Campus Total =
 56500 sf

NPC Item Estimated % Compliant, Overall Campus				
Equipment	Ceilings	Lights	Utilities	Sprinklers
10	10	10	10	10
0	0	0	0	0
100	100	100	100	0
0	0	0	0	0
100	100	100	100	100
85	77	77	77	77

% of total square footage requiring work to achieve NPC-4D, Level 1:

**22**%

Note: In addition, all equipment in Mechanical areas, including CUPS, roofs and penthouses, that serve critical care areas must be anchored.



#### NEW HOSPITAL I Market Assessment Findings

Adventist Mendocino Coast


- County Market projected to grow by .1% in Next ten years but Aging Population to grow in region by 13%
  - Drives overall bed need up by 4.4%

FUTURE PROJECTED PROGRAM (2031)
BEDS – ICU
BEDS – GENERAL ACUTE
ED BAYS
SURGERY – OPERATING ROOMS
СТ
RAD/FLUORO
ULTRASOUND
MRI/NM
ENDO

MARKET PROJECTIONS <sup>1</sup>		
4		
12		
14		
2		
1		
2		
1		
MOBILE		
2		

#### **NOTES:**

1. BASED ON MARKET ASSESSMENTS AND FACILITY PROJECTIONS 9.23.2022



- Primary Service Area (PSA) extends North-South 70 miles and only 10 miles inshore
  - Represents 84% of ED visits and 86% of Acute visits
- Secondary Service Area (SSA) extends to Mendocino County



## NEW HOSPITAL I Program

Adventist Mendocino Coast


FUTURE PROJECTED PROGRAM (2031)
BEDS – ICU
BEDS – GENERAL ACUTE
ED BAYS
SURGERY – OPERATING ROOMS
CT
RAD/FLUORO
ULTRASOUND
MRI/NM
ENDO

NEW HOSPITAL PROGRAM	EXISTING HOSPITAL PROGRAM	DELTA
4	4	
21	21	
14	8	+ 6
2	2	
0	0	
1	1	
0	0	
0	0	
2	1	+ 1



### NEW HOSPITAL I Proposed Square Footage

Adventist Mendocino Coast





### General | Pricing

Adventist Mendocino Coast

SDC 4D LIDGDADES
SPC 4D UPGRADES
NPC 4D UPGRADES
NEW HOSPITAL
CENTRAL UTILITY PLANT

SPC/NPC CAMPUS UPGRADES	NEW HOSPITAL CONSTRUCTION <sup>1</sup>
\$4,602,325	
\$7,532,272	
	\$84,733,741
	\$12,018,324

#### **TOTAL CONSTRUCTION COSTS**

#### Notes:

- 1. Assumes construction through 06/2028
- 2. Excludes NPC 5
- 3. Excludes Full Building NPC 4 Upgrades
- 4. SPC/NPC upgrades does not include any operational upgrades



## Questions

Adventist Mendocino Coast

